



ATTACHMENT 6: POST-MPC CASP POLICY AMENDMENTS

SOUTHWEST CASP REVISIONS

List of Revisions for May 17, 2021 Council Agenda

Purpose

The following is a list of requested revisions to the Council Agenda Version of the Southwest CASP

Number	Section	Page #	Revision
1	Section 13.3 Remove Interim Servicing Discussion	Page 80	Delete Last Paragraph In the event the required Stage 1 infrastructure (Cobblestone trunk and Lift Station No.8) are not in place at the time the NSP for Area B as shown on Figure 19: Growth Management Sequencing Strategy (12K Thousand Acres Plan) proceeds, this NSP area is still immediately serviceable by a sanitary gravity main connected across 24 Street SW at Chinook Gate Heath SW. This gravity main was installed in 2018 and has been sized to accommodate off peak flow contributions. Until such time as the required future local lift station is in place at the southeast corner of NSP Area B, a private lift station could be utilized. Where flows approach the gravity main capacity further discussion with the City of Airdrie for the immediate serviceability of NSP Area B is required. Further exploration of this option being possible at time of initiating the NSP.
2	Figure 17: Sanitary Services	Page 82	Insert Updated Figure 17: Sanitary Services showing revisions to UMP sanitary alignments and removal of sanitary lift station (temporary) option.
3	Section 13.2 Water Services Discussion	Page 78	Delete the following Paragraph: It is anticipated that NSP Area B as shown on Figure 11: Future Neighbourhood Structure Plan (NSP) Areas will be the first NSP to proceed within the Plan area. In the event the required infrastructure (booster station and new feedermain) is not in place at the time the NSP for Area B proceeds, the NSP area is immediately serviceable via the extension of two water distribution mains across 24 Street SW. If it is determined that boosting is required, the potential for one of the future pressure reducing valve locations along 24 Street SW to become a re-purposed version of a buried booster chamber should be explored.
4	Section 13.2 Water Services Policy	Page 78	Delete Policy 2 which reads: 2. Residual capacity or the need for boosting shall be confirmed at the NSP stage, based on regional servicing alignments and timing of feeder mains and reservoirs servicing all CASPs.

5	Figure 16: Water Services	Page 79	Insert Updated Figure 16: Water Services showing new reservoir site and feedermain relocated to 8 th street and 40 th Avenue ROW.
6	Section 13.2 Water Services Policy	Page 78	<p>Add the word “west” as indicated within paragraph 1:</p> <p>The second located in the High West PZ, at future 1 Avenue NW and 40 Street NW</p>
7	Section 13.2 Water Services Policy	Page 78	<p>Delete reference to North Central CASP and Rename Davy Creek CASP as follows within paragraph 2:</p> <p>This new feedermain and reservoirs will first service the Plan area, in parallel with servicing additional or upstream CASP areas; including the West Hills CASP and the North Central Davy Creek CASP.</p>
8	Section 13.3 Sanitary Services	Page 80	<p>Delete reference to the North Central CASP within paragraph 2 as follows in paragraph 2:</p> <p>Para 2 – This Airdrie Cobblestone Trunk runs alongside and services first the Southwest CASP, prior to servicing additional upstream CASPs; including the West Hills CASP and the North Central CASP.</p>